



NOTES:

1. CONCRETE: 4,000 PSI MINIMUM AFTER 28 DAYS.
2. REINFORCED STEEL CONFORMS TO LATEST ASTM A185
3. BUTYL RESIN SECTION JOINT CONFORMS TO LATEST ASTM C443 SPEC

E. F. SHEA
NEW ENGLAND
CONCRETE PRODUCTS, INC.

PUMP STATION
 DUPLEX PUMP PACKAGE
 WITH VALVE PIT