



ITEM NO.	DESCRIPTION	WEIGHT
DW-SSS	30" SUMP	6,409#
DW-3SS	3' STACKABLE (NO COVER)	2,008#

NOTES:

1. CONCRETE: 4,000 PSI MINIMUM AFTER 28 DAYS.
2. AVAILABLE IN H-20 LOADING.
3. CAPACITY INCREASES IN INCREMENTS OF 500 GALLONS FOR EACH 3' SECTION ADDED.

E. F. SHEA
 NEW ENGLAND
 CONCRETE PRODUCTS, INC.

DRY WELL CYLINDRICAL
 LEACHING CHAMBER
 STACKABLE